



ADVANCED MATERIALS & PROCESSES RESEARCH INSTITUTE, BHOPAL
FORMERLY : REGIONAL RESEARCH LABORATORY
(COUNCIL OF SCIENTIFIC & INDUSTRIAL RESEARCH)
Hoshangabad Road, Near Habibganj Naka, Bhopal – 462 026 (M.P.)

NOTICE INVITING QUOTATION Ref No.: 1(516)2023

Sealed Quotation are invited for following work at AMPRI, Bhopal. Contractors registered with State PWD, MES, CPWD, Railways and Govt. organization/ Semi Govt./ Autonomous organization/ CSIR and other reputed civil contractors for carrying out Civil works who have completed similar nature of work satisfactorily. The contractors are required to produce copy of PAN, GST No., Firm Certificate along with Quotation.

Name of Work	Estimated Cost (GST included)	EMD	Work completion period	Date of issue of quotation from AMPRI Website in enclosed format	Last date of receipt of quotation	Date of Opening
Civil work related to OWOL programme at AMPRI, Bhopal	249760.0	6000/-	15 days	11.05.2023 to 13.05.2023 at 5.30 PM	14.05.2023 at 3.00 PM	14.05.2023 at 3.30 PM

Quotation document will be downloaded in enclosed format between 11.05.2023 to 13.05.2023 up to 5.30 PM on all working days from period shown as above from the website www.ampri.res.in.

Quotation with rate valid for 90 day from the of opening will be received in sealed envelope by Head ESD AMPRI, Bhopal up to 14.05.2023 at 3.00 PM and opened on 14.05.2023 at 3.30 PM with name of work as shown above in presence of representatives if any. In case of poor response opening date may be extended.

The Director AMPRI, Bhopal reserves the right to reject any or all the Quotation or to accept them in part without assigning any reasons.

**Head
Engineering Services Division**

Quotation

Date :

To,
The Director
AMPRI,
Bhopal

Name of work : - Civil work related to OWOL programme at AMPRI,Bhopal

S.No.	Name of Item	Unit	Quantity	Rate	Amount
1	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	sqm	50.00		
2	Wall painting with premium acrylic emulsion paint of interior grade(Plastic Paint), having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour.and colour. Two or coats.	sqm	50.00		
3	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) jointing with grey cement slurry @ 3.3kg/sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600 mm	sqm	70.00		
4	Providing and laying 60mm thick factory made rubber moulded cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of stone dust filling the joints with fine sand and sides shall be locked with concrete 1:2:4 etc. all complete as per the direction of Engineer-in-charge.	sqm	250.00		

5	External painting by ACE /APEX or equivalent exterior paint including scraping the old surface and filling the crack by crack seal equivalent in desired colour and shade including projection and wall as per instruction and direction of E-in-C. (TWO or more coat)	sqm	820.00		
6	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :	sqm	200.00		
				Total Rs.	

Seal & Signature of Contractor
Address :

दिनांक 11.5.2023

विषय:- NIQ को एम्प्री वेबसाइट पर अपलोड करने हेतु।

Ref No.: (1(516)2023 Work.

उपरोक्त संबंध में लेख है कि Civil works related to OWOL Programme at AMPRI, Bhopal का कार्य हेतु NIQ को एम्प्री वेबसाइट पर अपलोड करना है जिससे अधिक से अधिक लोग भाग ले सकें।

(अ.अ.बख्श)

सलंगन :- NIQ

सूचना प्रादयोगिकी विभाग